BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT34585

Providing CC Camera and improvements to SWM in Ward No.03

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. CHARAN N S	
				In figures	In words
1	4.00	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP , 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and	Nos	25000.00	Rupees Twenty Five Thousand Only
2	1.00	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	75000.00	Rupees Seventy Five Thousand Only
3	1.00	Supplying ,installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	275000.00	Rupees Two Lakh(s) Seventy Five Thousand Only
4	1.00	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	25000.00	Rupees Twenty Five Thousand Only
5	1.00	Supplying ,installation ,Commissioning and Testing D-Link 24-Port Gigabit Switch With 4 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	35000.00	Rupees Thirty Five Thousand Only
6	1.00	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	30000.00	Rupees Thirty Thousand Only
7	1.00	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	65000.00	Rupees Sixty Five Thousand Only
8	1.00	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	15000.00	Rupees Fifteen Thousand Only
9	230.00	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	200.00	Rupees Two Hundred Only
10	1.00	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	25000.00	Rupees Twenty Five Thousand Only
11	1.00	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	10000.00	Rupees Ten Thousand Only
12	1.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	10000.00	Rupees Ten Thousand Only
13	1.00	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	8000.00	Rupees Eight Thousand Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Rates quoted by Sri. CHARAN N S	
				In figures	In words
-	1.00	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	3000.00	Rupees Three Thousand Only
15	1.00	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	Nos	7000.00	Rupees Seven Thousand Only
16	1.00	Providing and Fixing HDMI Cables 10 Mtrs inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	7000.00	Rupees Seven Thousand Only
17		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone

8/3/19